BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16489

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

Providing and Fixing New Street Signage Boards in Ward No. 08, Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Bharath K.S.	
				In Figures	In Words
1	72.57	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	cum	75.6	Rupees Seventy Five and Sixty Paise Only
2	72.57	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	73.57	Rupees Seventy Three and Fifty Seven Paise Only
3	18.14	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregares @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5064.12	Rupees Five Thousand Sixty Four and Twelve Paise Only
4	54.43	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5852.52	Rupees Five Thousand Eight Hundred Fifty Two and Fifty Two Paise Only
5	252.00	Supplying of MS steel name boards as per approved design and specification complete with all leads and lifts as per the direction of the Engineer-in-charge of the work (Data rate approved)	No.	5203	Rupees Five Thousand Two Hundred Three Only
6	263.61	KSRB- 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	sqm	82.08	Rupees Eighty Two and Eight Paise Only
7	263.61	KSRB- 15-18.1 : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after thoroughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, laour complete as per specifications	sqm	28.08	Rupees Twenty Eight and Eight Paise Only
8	189000.00	KSRRBM800-9: Painting new letter and figures of any sshade with synthetic enamel paint black or nay other approved colour to give an even shade complete as per specifications ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half)	cm	0.7	and Seventy Paise Only

9	10.00	Providing and fixing of Ornamental name boards (providing and fixing of ornamental name boards of size 2.10x0.50m) and 2 column of size 0.15x0.15m of height 1.23m o feach boards of CC 1:1.5:3 with necessary centering and form work, smooth finishing with reinforcement etc., including fabrication charges, painting letters (Bangalore Mahanagara Palike, ward No. and BBMP Emblem) earthwork excavation, concreting and transportation charges from manufacturing yard to the wrok site etc, complete with all leads and lifts loading and unloading and any incidental charges and as per the drawing and specification and direction of the Engineer-in-charge of the work	No.	8050	Rupees Eight Thousand Fifty Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92